BRUHAT BANGALORE MAHANAGARA PALIKE

Item No.04

Modified Approved Shedule-B

Tender Notification No: BBMP/ EE /Btp/Ten/05/2012-13 Dated: 30-07-2012

Name of Work: Repair of Govt School Building at Jakkur, Ward No. 5, Byatarayanapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of DILIP KUMAR N S	
				In Figures	In Words
1	227.11	Dismantling cement concrete flooring or plain cement concrete work including removing and conveying the debris to distance upto 200 m (within average thickness of 15 cms), as per specifications.and directions of Engineer In Charge	Sqm	**38.94**	Rupees Thirty Eight and Ninety Three Paise Only
2	863.51	Dismantling plastering and removing the debris with a lead upto 200m, as per specifications.and directions of Engineer In Charge	Sqm	**16.66**	Rupees Sixteen and Sixty Five Paise Only
3	24.65	Dismantling weather proof course and removing and conveying the debris to a distance upto 200m, as per specifications.and directions of Engineer In Charge	Cum	**333.17**	Rupees Three Hundred Thirty Three and Sixteen Paise Only
4	30.62	KSRB-4-1.3 : Providing and laying in position **plain cement concrete of mix M 7.5** withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing completeas per specifications.and directions of Engineer In Charge	Cum	**3729.48**	Rupees Three Thousand Seven Hundred Twenty Nine and Forty Seven Paise Only
5	386.89	KSRB 14.10.2 : **Flooring with 25mm to 40mm thick polished shahabad** slabs using mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed with cement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing complete as per specifications. Page No. 110/ Item No. 14.16 / PWD SR 2011-12	sqm	**866.03**	Rupees Eight Hundred Sixty Six and Three Paise Only
6	5.18	KSRB 6-2.3 Providing and constructing **burnt brick masonry** with approved quality of non-modular bricks of standard size of class designation 50 (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.and directions of Engineer In Charge	Cum	**4576.82**	Rupees Four Thousand Five Hundred Seventy Six and Eighty Two Paise Only

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of DILIP KUMAR N S	
				In Figures	In Words
7	227.11	KSRB 15.3.13 : Providing 12**mm thick cement plaster** in single coat with **cement mortar 1:3, to ceiling** including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.and directions of Engineer In Charge	Sqm	**142.82**	Rupees One Hundred Forty Two and Eighty Two Paise Only
8	435.83	KSRB 15-3.7:- Providing **18mm thick cement plaster** in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specificationsPage No. 120/ Item No. 15.16/ PWD SR 2011-12	sqm	**142.05**	Rupees One Hundred Forty Two and Five Paise Only
9	227.11	KSRB 15.7: Providing **lime rendering** for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications.and directions of Engineer In Charge	Sqm	**16.06**	Rupees Sixteen and Five Paise Only
10	278.51	KSRB 15-3.7:- Providing **18mm thick cement plaster** in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.and directions of Engineer In Charge	Sqm	**142.05**	Rupees One Hundred Forty Two and Five Paise Only
11	662.93	KSRB 15.15.1: Providing and applying painting in two coats with **plastic emulsion paint** of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth cost of materials, labour, completeas per specifications.and directions of Engineer In Charge	Sqm	**66.23**	Rupees Sixty Six and Twenty Three Paise Only
12	278.51	KSRB 15-16 : Providing and finishing external walls in two coats with **waterproof cement paint** of approved brand and shade to given an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications.and directions of Engineer In Charge	Sqm	**60.21**	Rupees Sixty and Twenty One Paise Only
13	85.56	KSRB 15-17.6: Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with **enamel paint** to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications.and directions of Engineer In Charge	Sqm	**73.26**	Rupees Seventy Three and Twenty Five Paise Only

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of DILIP KUMAR N S	
				In Figures	In Words
14	59.50	KSRB 8.6-7 : Providing and fixing on wall surface 4.0kg/sq.cm H.D.P.E rain down water pipes 90mm outer dia approved make and brand with necessary specials like shoes bends and offsets fixed with iron clamps, walls plugs, screws, including cost of materials, labour, complete as per specifications. **including cost of materials, labour, curing complete as per specifications.and directions of Engineer In Charge**	m	**325.14**	Rupees Three Hundred Twenty Five and Fourteen Paise Only
15	16.20	"Supplying and fixing pressed steel window frame of size 100x50mm manufacture from 1.25 mm thick carbon steel or imported steel strips with neat mitred joints at 900degree for window openings and shall be suitable to fix M.S grills as per design and drawings using 12mm dia roads at 100mm centre to centre horizontally and two members of M.S flats of 6mmx40mm size at 150mm apart, welded into a frame of 6mmx40mm size M.S flats with 16mm size lugs, and 8nos, of 100mm size hinger, 4nos of butt stay pins and 4nos, tower bolts and shutters half paneled and half glazed with shutters made out of seasoned honne wood, styles of 30mm thick and 100 mm width and rails of 30mm thick and 100 mm width and using 4mm thick pin headed glass and panel, filling with 12mm thick particle board of exterior grade bonded with phenol formal dehide resin and the shutter shall be rot proof vermin proof, heat resistant guaranteed against shrinkage, warp age and such other defects for a period of 3 years, this shall be as per approved drawicuring complete as per specifications.and directions of Engineer In Chargeg painting with 2 coats enamel paint over one coat of primer,	Sqm	**4028.00**	Rupees Four Thousand Twenty Eight Only
16	3.15	Supply and fixing pressed steel door frames size 125x65 mm manufacture from 1.25mm thick carbon steel or imported steel strips with mitred joints of 900 for door openings and sutters made out of seasoned honne wood, styles of 30mm, thick with lock rail of 160mm, width, top and side rails of 100mm, width width and bottom rails of 250 mm width and panel filling with 12mm thick particle board of exterior grade bonded with phenol formal dehide resin and the shutter shall be not proof, vermin proof, heat resistant guaranteed against shrinkage, warpage and such other defects for a period of 3 years, this shall be as per approved drawings, specification and direction including cost of conveyance, manufacturing, painting wit enamel paint 2 coats over primer coat, cost of labour for all items of work, machinery, equipment and all other incidental charges with all lead, lift, loading and unloading etc, complete the hollow portion of the frame to be filled with cement concrete1:2:4. **including cost of materials, labour,**	Sqm	**3710.00**	Rupees Three Thousand Seven Hundred Ten Only
17	246.50	KSRB 15-3.10 : Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry & concrete surface including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. **including cost of materials, labour, curing complete as per specifications.and directions of Engineer In Charge**	Sqm	**177.02**	Rupees One Hundred Seventy Seven and Two Paise Only

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of DILIP KUMAR N S	
				In Figures	In Words
18	7.91	KSRB- 4-1.5 : Providing and laying in position plain cement concrete of **mix M20 with OPC cement @ 300 kgs, with 20mm** and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, including cost of materials, labour, curing complete as per specifications.and directions of Engineer In Charge	cum	**4846.32**	Rupees Four Thousand Eight Hundred Forty Six and Thirty Two Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92